No.	Items of work	Per	Quantity
	Anjaneyaswamy Temple.		
1	Removing the present shed	Lumpsum Rs.	..
2	Earth work	Cyds.	16
2 (a)	Concrete for foundation	C.ft.	213
3	Burnt Stone in mortar	,,	1054
4	Burnt Stone slabs 6″ thick dressed and fixed	Sqr. ft.	135
5	Cut stone work pillars and capitals	C.ft.	111
6	Do (Cut stone beams)	,,	83
7	Burnt stone slabs 6″ dressed and fixed on top	S.ft.	226
8	Chunam concrete for top with smoothening and ½″ thick cement plastering	C.ft.	139
9	Ornamental parapet in brick in chunam with 9″ cornice below and coping at top complete	R.ft.	68
10	Flooring with concrete with smoothening and cement-wash	Sqr.	81
11	Flooring with Cuaddapah slabs on 3″ concrete bed with cement pointing	,,	36
12	Cement pointing	,,	9·14
13	Teak wood 2″ thick battened door including cutting groves in slabs locking arrangements, etc.	S.ft.	18
14	Clearing and removing debris and unforeseen charges	Lumpsum	..

V. V. PATANKAR,
Executive Engineer.

HASSAN DIVISION.

Notification, dated 20th July 1934.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 13th August 1934 for Constructing a Local Fund Dispensary Building at Hole-Narsipur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing a Local Fund Dispensary at Hole-Narsipur" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12 Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract Estimate for Constructing a Local Fund Dispensary at Hole-Narsipur, Hassan District.

Sl. No.	Items of work	Per	Quantity	Rate
	Main Building.			
1	Earth work excavation and filling in basement ..	C.yd.	115	
2	Concrete in mortar for foundation	C.ft.	1,110	
3	Burnt size stone in mortar foundation and basement ..	,,	3,449	
4	Burnt brick in mortar	,,	3,750	
5	Burnt stone slabs 6″ dressed and fixed	S.ft.	713	
6	Arch work (brick in mortar)	C.ft.	49	
6a	Cement concrete blocks	,,	25	
7	Teak wood panelled door 1¼″ including top ventilators, bolts, hinges and brass locks, etc., complete ..	S.ft.	286	
8	Teak wood windows with single side shutters and top ventilator ½ glazed and ½ panelled in 4 halves with iron bars, hinges, clamps, etc., complete	,,	342	
9	Teak wood glazed ventilators with hooks, hinges and iron bars, etc.	,,	16	
10	Teak wood circular ventilators glazed, etc. ..	,,	21	
11	Teak wood shelves with plank and panelled shutters, hinges, hooks, etc., complete	,,	95	
12	Teak wood wrought and put-up with wood oiling ..	C.ft.	131.79	
13	Roofing with 1st class Mangalore Tiles on teak reepers, etc., complete including wood oiling repeers and fixing the end tiles	Sqr.	26.87	
14	Ridge tiles set in mortar	R.ft.	153	
15	Plastering with mortar	Sqr.	77.22	
16	Cement pointing	,,	5.37	
17	White and colour washing	,,	77.22	
18	Flooring with 1st class Mangalore Tiles on 3″ concrete and cement pointing, etc., complete	Sqr.	10.00	
19	Flooring with burnt stone slabs, dressed over 3″ concrete and cement pointing	,,	4.91	
20	Teak wood planking for valley 3′ wide	S.ft.	227	
21	Plain zinc sheet 3 feet wide for valleys as per planking	,,	227	
22	Teak wood ornamental eave boards with painting ..	R.ft.	298	
23	Teak wood pendents big with painting	Each	14	
24	Do finials with painting	,,	3	
25	Silicate painting 2 coats for doors and windows outside only	Sqr.	5.51	
26	Varnishing 2 coats to inside of doors and windows ..	,,	9.31	
27	Binding walls at gable 1′ high and 9″ thick with burnt brick in mortar	R.ft.	56	
28	Teak wood screen with door ways and painting ..	S.ft.	98	
29	Tarring wood work	Sqr.	..	
30	Constructing sinks with outlets, etc., complete ..	Each	4	
31	Drainage	R.ft.	..	
32	Levelling the site and forming	C.yd.	..	
33	Providing with brackets at windows for delivery of medicines with plank, etc.	S.ft.	..	
34	Stone pillars 6″ square with base and capitals, etc., complete	Each	6	
	Latrine.			
1	Earth work excavation and filling in basement ..	C.yd.	4	
2	Burnt stone in mortar	C.ft.	113	
3	Burnt brick in mortar	,,	156	
4	Coping with do	R.ft.	38	
5	Plastering with mortar	Sqr.	4.23	
6	White and Colour washing	Sqr.	4.23	
7	Constructing a cistern and providing with brackets and cast iron outlet and inlet pipes	Lumpsum		

Sl. No.	Items of work	Per	Quantity	Rate
8	Clearing site and tarring sides	Lumpsum		
9	Flooring with $1\frac{1}{2}$″ cement concrete on 3″ lime concrete	Sqr.	0.65	
	Kitchen.			
1	Earth work excavation and filling in basement	C.yd.	4	
2	Burnt stone in mortar foundation and basement	C.ft.	176	
3	Burnt brick in mortar	,,	272	
4	Burnt stone slabs 6″ dressed and fixed	S.ft.	17	
5	Plastering with mortar	Sqr.	5.29	
6	White and colour washing	,,	5.29	
7	Cement pointing	,,	0.45	
8	Teak wood wrought and put-up with wood oiling	C.ft.	10.23	
9	Roofing with 1st class Mangalore Tiles on teak reepers with wood oiling to reepers and end tiles fixed	Sqr.	2.21	
10	Ridge tiles set in mortar	R.ft.	15	
11	Ventilating tiles	Each	4	
12	Teak wood battened doors with hinges, bolts, etc., complete	S.ft.	18	
13	Teak wood windows with shutters, iron bars, hinges and hooks, etc., complete	,,	5	
14	Flooring with dressed burnt stone slabs on 3″ concrete and cement pointing	Sqr.	0.70	
15	Chocalate painting 2 coats	,,	0.46	
16	Binding wall at gable 1 foot high and 9″ thick with brick in mortar and plastering	R.ft.	28	
17	Clearing site and building chimney, etc., complete	Lumpsum		
	Filling up pits.			
1	Filling the pits with earth and forming	C.yd.	..	
	Dead House.			
1	Earth work excavation and filling in basement	C.yd.	24	
2	Chunam mortor concrete	C.ft.	143	
3	Burnt stone in clay foundation and basement	,,	403	
4	Burnt brick in clay	,,	380	
5	Do in mortar	,,	113	
6	Plastering with mortar	Sqr.	9.70	
7	Teak wood wrought and put-up with wood oiling	C.ft.	27.70	
8	Roofing with 1st class Mangalore Tiles, etc., complete	Sqr.	3.90	
9	Ridge Tiles set in mortar	R.ft.	18	
10	Teak wood windows with panelled shutters, iron bars, etc., complete	S.ft.	48	
11	Burnt stone slabs 6″ dressed and fixed	S.ft.	76	
12	Stone flagging or 3″ concrete, etc., complete including cement pointing	Sqr.	1.57	
13	Chunam boarder over roof	R.ft.	42	
14	Teak wood door with panelled shutters, hinges, etc., complete	S.ft.	30	
15	Silicate painting	Sqr.	1.76	
16	Providing and fixing G. I. pipes for drain	R.ft.	$1\frac{3}{4}$	
17	Stone pillars $3' \times \frac{3}{4}' \times \frac{3}{4}'$, dressing and fixing, etc., complete	S.ft.	9	
18	Armoured concrete slab 6″ thick with nice cement plastering, etc., complete	C.ft.	12	
19	White washing	Sqr.	9.70	
20	Teak wood eave board 9″ with painting	R.ft.	36	
21	Expanded metal with teak wood frame, etc., complete	S.ft.	$18\frac{3}{4}$	

N. LAKSHMINARASIMHAIYA,
Executive Engineer.